



Test Report: APC-25-350

25W Single Output Switching Power Supply

■ DESIGN VERIFY TEST

Output Function Test

Input Function Test

Protection Function Test

Component Stress Test

■ SAFETY & E.M.C. TEST

Safety Test

E.M.C. Test

■ RELIABILITY TEST

ENVIRONMENT TEST

■ DESIGN VERIFY TEST

OUTPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	RIPPLE & NOISE	V1 : 300 mVp-p (Max)	I/P : 230VAC O/P : FULL LOAD Ta : 25°C	V1 : 80 mVp-p (Max)	P
2	CONSTANT CURRENT REGION	V1= 25 V ~ 70 V	I/P : 230VAC O/P : CV MODE Ta : 25°C	O/P= 25V : 0.361 A O/P= 69V : 0.360 A	P
3	OUTPUT VOLTAGE TOLERANCE	V1 : 5 %~ -5 % (Max)	I/P : 100 VAC / 264 VAC O/P : FULL/ MIN LOAD Ta : 25°C	V1 : 0.371 %~ -0.014 %	P
4	LINE REGULATION	V1 : 1 %~ -1 % (Max)	I/P : 100 VAC ~ 264 VAC O/P : FULL LOAD Ta : 25°C	V1 : 0 %~ -0.014 %	P
5	LOAD REGULATION	V1 : 3 %~ -3 % (Max)	I/P : 230 VAC O/P : FULL ~MIN LOAD Ta : 25°C	V1 : 0.014 %~ -0.014 %	P
6	SET UP TIME	230VAC : 1500 ms (Max) 115VAC : 1500 ms(Max)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC/ 289.39 ms 115VAC/ 298.89 ms	P
7	RISE TIME	230VAC : 30 ms (Max) 115VAC : 30 ms (Max)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC/ 25.37 ms 115VAC/ 23.93 ms	P
8	HOLD UP TIME	230VAC : 20 ms (TYP) 115VAC : 12 ms (TYP)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC/ 82.09 ms 115VAC/ 20.06 ms	P
9	OVER/UNDERSHOOT TEST	< ±5%	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	TEST : <5 %	P
10	DYNAMIC LOAD	V1 : 7000 mVp-p	I/P : 230 VAC (1).O/P : FULL /Min LOAD 90%DUTY/ 1KHZ (2).O/P : FULL /Min LOAD 50%DUTY/ 120HZ Ta : 25°C	(1) 366 mVp-p (2) 2820 mVp-p	P

INPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	INPUT VOLTAGE RANGE	90VAC~264 VAC	I/P:TESTING O/P:FULL LOAD Ta:25°C	87 V~ 264 V	P
			(1)I/P: LOW-LINE-3V= 87 V HIGH-LINE+15%= 300 V O/P:FULL/MIN LOAD ON: 30 Sec . OFF: 30 Sec 10MIN (2) I/P:230VAC ON: 0.5 Sec . OFF: 0.5 Sec 20MIN (AC POWER ON/OFF NO DAMAGE)	TEST: (1) OK (2) OK	
2	INPUT FREQUENCY RANGE	47HZ ~63 HZ NO DAMAGE OSC	I/P : 90 VAC ~ 264 VAC O/P : FULL~MIN LOAD Ta : 25°C	TEST : OK	P
3	EFFICIENCY	83% (TYP)	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	84.18 %	P
4	INPUT CURRENT	230V/ 0.4 A (TYP) 115V/ 0.8 A (TYP)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	I = 0.278 A/ 230 VAC I = 0.436 A/ 115 VAC	P
5	INRUSH CURRENT	230V/ 70 A (TYP) 115V/ 35 A (TYP) COLD START	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	I = 29.8 A/ 230 VAC I = 14.7 A/ 115 VAC	P
6	LEAKAGE CURRENT	< 0.25 mA / 240 VAC	I/P : 240 VAC O/P : Min LOAD Ta : 25°C	L-CASE : 0.003 mA N-CASE : 0.003 mA	P

PROTECTION FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	OVER VOLTAGE PROTECTION	CH1 : 76 V ~ 94 V	I/P : 230 VAC I/P : 115 VAC O/P : MIN LOAD Ta : 25°C	84.1 V/ 230 VAC 84.1 V/ 115 VAC Shut down o/p voltage, re-power on to recover	P
2	SHORT PROTECTION	SHORT EVERY OUTPUT 1 HOUR NO DAMAGE	I/P : 264 VAC O/P : FULL LOAD Ta : 25°C	NO DAMAGE Hiccup mode	P

COMPONENT STRESS TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
----	-----------	---------------	----------------	--------	---------

1	Power Transistor (D to S) or (C to E) Peak Voltage	Q1 Rated : NDF06N60ZG : 600 V/ 6.0 A	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on (2) Output Short (3)Full load continue Ta : 25°C	(1) 512 V (2) 442 V (3) 500 V	P
2	Diode Peak Voltage	D103 Rated : ER306: 600 V/ 3.0 A	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on (2)Output Short (3)Full load continue Ta : 25°C	(1) 392 V (2) 350 V (3) 402 V	P
3	Input Capacitor Voltage	C5 Rated : 47u/420V 105°C 18*20 KM	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on /Off (2) Min load Turn on /Off (3)Full Load /Min load Change Ta : 25°C	(1) 392 V (2) 372 V (3) 372 V	P
4	Control IC Voltage Test	U 1 Rated : NCP1200D100R2G: 16V (MAX)	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on /Off (2) Min load Turn on /Off (3)Full Load /Min load Change Ta : 25°C	(1) 11.8 V (2) 11.8 V (3) 11.6 V	P

■ SAFETY & E.M.C. TEST

SAFETY TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	WITHSTAND VOLTAGE	I/P-O/P : 3 KVAC/min	I/P-O/P : 3.6 KVAC/min Ta : 25°C	I/P-O/P : 2.111 mA NO DAMAGE	P
2	ISOLATION RESISTANCE	I/P-O/P : 500VDC>100MΩ	I/P-O/P : 500 VDC Ta : 25°C/70% RH	I/P-O/P : >9999 MΩ NO DAMAGE	P

E.M.C TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	HARMONIC	EN61000-3-2 CLASS A	I/P:230VAC/240VAC/220VAC50HZ O/P:100%LOAD CLASS A Ta:25°C	PASS	P
2	CONDUCTION	EN55022 CLASSB	I/P: 230 VAC (50HZ)/115V[60HZ] O/P:FULL LOAD Ta:25°C	PASS Test by certified Lab	P
3	RADIATION	EN55022 CLASSB	I/P: 230 VAC (50HZ)/115V[60HZ] O/P: FULL LOAD Ta:25°C	PASS Test by certified Lab	P

4	E.S.D	EN61000-4-2 LIGHT INDUSTRY AIR:8KV / Contact:4KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A	P
5	E.F.T	EN61000-4-4 LIGHT INDUSTRY INPUT: 1KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A	P
6	SURGE	IEC61000-4-5 INDUSTRY L-N :2KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A	P
7	Test by certified Lab & Test Report Prepare				

■ RELIABILITY TEST

ENVIRONMENT TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	TEMPERATURE RISE TEST	MODEL : APC-25-500 1. ROOM AMBIENT BURN-IN : 2.5 HRS I/P : 230VAC O/P : 95% LOAD Ta=33.2 °C 2. HIGH AMBIENT BURN-IN : 3.5 HRS I/P : 230VAC O/P : 95% LOAD Ta=44.1 °C			P
2	LOW TEMPERATURE TURN ON TEST	TURN ON AFTER 2 HOUR	I/P : 264VAC/100VAC O/P : 95 % LOAD Ta= -30°C	TEST : OK	P
3	HIGH HUMIDITY HIGH TEMPERATURE HIGH VOLTAGE TURN ON TEST	AFTER 12 HOURS IN CHAMBER ON CONTROL 40 °C NO DAMAGE	I/P : 264 VAC O/P : 95% LOAD Ta= 40 °C HUMIDITY= 95 %R.H	TEST : OK	P
4	TEMPERATURE COEFFICIENT	± 0.2 % (0-50°C)	I/P : 230 VAC O/P : 95% LOAD	± 0.004 % (0-50°C)	P

5	STORAGE TEMPERATURE TEST	1. Thermal shock Temperature : -45°C~ +85°C 2. Temperature change rate : 25°C / MIN 3. Dwell time low and high temperature : 30 MIN/EACH 4. Total test cycle : 5 CYCLE 5. Input/Output condition : STATIC	OK	P
6	THERMAL SHOCK TEST	1. Thermal shock Temperature : -35°C~ +45°C 2. Temperature change rate : 25°C / MIN 3. Dwell time low and high temperature : 30 MIN/EACH 4. Total test cycle : 10 CYCLE 5. Input/Output condition : 230VAC/Full Load AC ON/OFF TEST turn on 58sec ; turn off 2sec	OK	P
7	VIBRATION TEST	1 Carton & 1 Set (1) Waveform : Sine Wave (2) Frequency : 10~500Hz (3) Sweep Time : 12min/sweep cycle (4) Acceleration : 2G (5) Test Time : 72min in each axis (X.Y.Z) (6) Ta : 25°C	TEST : OK	P
8	CAPACITOR LIFE CYCLE	APC-25-500 :SUPPOSE C106 IS THE MOST CRITICAL COMPONENT (1) I/P : 230VAC O/P : FULL LOAD Ta=25 °C LIFE TIME (2) I/P : 230VAC O/P : FULL LOAD Ta=40 °C LIFE TIME (3) I/P : 230VAC O/P : 75% LOAD Ta=40 °C LIFE TIME	(1) 168792.8 HRS (2) 48617 HRS (3) 109388.3 HRS	P
9	MTBF	Conducted by Parts Stress Analysis Prediction 4955.9K hrs min. Telcordia SR-332 (Bellcore) ; 504.9K hrs min. MIL-HDBK-217F (25°C)		P
10	DMTBF/Accelerated Life Test	Demonstration Mean Time Between Failure(Expected Life) : 20,000 hours @ Tcase 75°C ; 50,000 hours @ Tcase 60°C		P

DATE	SAMPLE	TEST RESULT	TESTER	APPROVAL
2012/05/30	PRODUCT SAMPLE	PASS	ZOULF	HOWAY

2009/08/04 A50-F023